

Product Description

Zero Cross or Random-on Switching

◆ Rated Current: 25A

* Rated Voltage: 240VAC, 600VAC Input Range: 3-32VDC or 4-32VDC

SCR output

Internal RC Protection Circuit

IP20 touch-safe housing

Integrated Heatsink

+ EN50022 35mm DIN Rail mount



Ordering Information

KSK

240

D

25

Switching Mode

Over Voltage Protection

KSK Series

Load Voltage 240: 240VAC 600: 600VAC Control Voltage Rated Current D: DC control 25: 25Amp

None:Zero Crossing R: Random-on

Customer Code None: Without TVS T: With TVS

Heatsink

K: KHS-K90 heatsink L: KHS-L90 heatsink

Note: The code for heatsink will not display on the product marking.

List of Models								
Rated Load	Blocking	0	Zero-on		RANDOM-ON			
Voltage	Voltage ⁽¹⁾	Control Voltage	-	with TVS		with TVS		
240:240VAC	800VPK	D: 3∼32VDC	KSK240D25	KSK240D25-T	KSK240D25R	KSK240D25R-T		
600:600VAC	1200VPK	D: 4~32VDC	KSK600D25	KSK600D25-T	KSK600D25R	KSK600D25R-T		

Technical Specifications Input Specifications (Ta=25°C) KSK240D...series $3\sim$ 32VDC Control Voltage Range KSK600D....series $4\sim$ 32VDC Maximum Input Current(2 20mA(@32VDC) KSK240D...series 3VDC Must Turn-on Voltage KSK600D...series 4VDC Must Turn-off Voltage 1VDC Maximum Reverse Voltage -32VDC










Technical Specifications

Output Specifications(Ta=25°C)					
	KSK240D series	24~280VAC			
Load Voltage Range (45∼65Hz)	KSK600D series	24~660VAC			
DI 1: VII (1)	KSK240D series	800Vpk			
Blocking Voltage ⁽¹⁾	KSK600D series	1200Vpk			
Breakdown Voltage of Internal TVS	KSK240DT series	480V			
breakdown voltage of internal 1 v3	KSK600DT series	1100V			
Max. Operational Current AC-51@25°C(3)	with KHS-K90 heatsink	30A			
Wax. Operational Current AC-31@23 CV	with KHS-L90 heatsink	35A			
Max. Operational Current AC-51@40°C ⁽³⁾	with KHS-K90 heatsink	25A			
Max. Operational Current AC-31@40 CM	with KHS-L90 heatsink	30A			
Min. Load Current		100mA			
Surge Current (@10ms)		800Apk			
Max. I²t For Fusing (@10ms)		3200A ² s			
Max. Turn-on Time	KSKD25Rseries	1ms			
Max. Turn-on Time	KSKD25series	1/2cycle+1ms			
Max. Turn-off Time		1/2cycle+1ms			
Max. Off-State Leakage Current (@ Rated Voltage)		3mA			
Max. On-state Voltage Drop (@ Rated Current)		1.5Vrms			
Min. Off-state dv/dt		1000V/µs			

General Specifications(Ta=25°C)						
Dialoctric Strongth (FO/SOLL)	Input/Output		4000Vrms			
Dielectric Strength(50/60Hz)	Input,Output/Heatsink	!	4000Vrms			
Insulation Resistance(@500V)			1000ΜΩ			
Ambient Operating Temperature Range			-30°C ∼ +80°C			
Ambient Storage Temperature Range			-30°C ∼ +100°C			
Maight/Timical	with KHS-K90 heatsink		190g			
Weight(Typical)	with KHS-L90 heatsink		260g			

- (1) For products with built-in TVS, please refer to TVS protection voltage;
- (2) The input current value is related to the input voltage and ambient temperature. Please refer to "input current v.s. input voltage curve" for details;
- (3) The maximum load current is related to ambient temperature and product installation spacing. For details, please refer to "Temperature curve".

Installation














Wiring Diagram

Unit:mm,Tolerances:±0.3mm


KSK...25...-K series









KSK...25...-L series








Input current vs. input voltage













Derating vs. spacing curves






Thermal Curve

KSK...25...-K series



KSK...25...-L series









Important Notice

- 1. SSR's carrying load capacity is related to the operation ambient temperature and heat dissipation condition, when there are many pieces SSR installed closely, please refer to the Thermal Derating Curve for derating.
- 2. When connection wiring to SSR, please ensure screws are torqued down properly. Recommended torque for input screw is (3.1-4.4)lbf·in/(0.35-0.5)N·m, output screw is (8.7-12.1)lbf·in/(0.98-1.37) N·m.

! Warnings

- 1. The product may be hot during use, allow the product to cool before touching.
- 2. Disconnect all power before installing or working with this equipment.
- 3. Verify all connections and replace all covers before turning on power.





